



5341 Perimeter Parkway Ct. Montgomery AL 36116

Email : tkelectricoffice@gmail.com

QUOTATION / 견 적 서

1	SERVICE PROVIDER		8	PO NUMBER / DATE OF QUOTATION	
TK ELECTRIC LLC 763 Us Highway 80, Eden, GA 31307			TKM101062		7/24/2026
2	CONSIGNEE		9	REMARKS	
ACS					
3	CONTACT				
Mr.Bryan Schneider bschneider@acscm.com					
4	PROJECT NAME	5	SERVICE PERIOD		
General Assembly Emission lab Electric & Control Work		2026.07.01 ~ 2026.12.31			
6	PROJECT BUILDING/ AREA	7	PROJECT LOCATION	10	PROJECT MANAGER
G.Assembly		1500 Genesis Drive, Ellabell, Georgia 31308		JUNG G. PARK	10
					SAFETY MANAGER
					CHRIS HILGER
12	PROJECT NAME & DESCRIPTION				
General Assembly Emission lab Electric & Control Work		QTY		UNIT	
1. ELECTRICAL WORK		1		LOT	
2. INSTRUMENT WORK					
13	CONDITIONS AND TERMS		MATERIALS		\$ 64,175.51
(결제 조건) :			LABOR		\$ 29,060.76
			EXPENSE		\$ 7,622.08
			SUB. TOTAL		\$ 100,858.36
			MANAGEMENT		\$ 10,085.84
			G. TOTAL		\$ 110,944.19
			ROUND OFF		\$ (44.19)
APPROVED BY :			FINAL AMOUNT		\$ 110,900.00

DATE : Friday, July 24, 2026

TAE K. KIM / PRESIDENT

TK ELECTRIC LLC.

Bill of Quantities

PROJECT : General Assembly Emission lab Electric & Control Work
CONSTRUCTION PERIOD : 2026.07.01 ~ 2026.12.31
SUBCONTRACTOR : TK ELECTRIC LLC.

품 명 DESCRIPTION OF WORK	규 격 SPECIFICATION	단위 UNIT	수 량 Q'ty	ITEM PRICE PER ITEM			Bill of Quantity		ITEM PRICE PER CLASSIFICATION			비 고 REMARKS
				MATERIAL	LABOR	EXPENSE	단 가 Unit Price	금액 Amount	MATERIAL	LABOR	EXPENSE	
■ Direct cost												
1. General Assembly Emission lab Electric & Control Work												
0101. ELECTRICAL WORK		L/S	1.00	59,184.99	24,305.80	6,817.70		90,308.50	59,184.99	24,305.80	6,817.70	
0102. INSTRUMENT WORK		L/S	1.00	4,990.52	4,754.96	804.38		10,549.86	4,990.52	4,754.96	804.38	
■ MANAGEMENT								10,085.84				
Sub Total								110,944.19	64,175.51	29,060.76	7,622.08	
Round off								(44.19)				
Grand Total								110,900.00				
1. General Assembly Emission lab Electric & Control Work												
0101. ELECTRICAL WORK												
POWER DISTRIBUTION PANEL	Main 400AF 480/277V, 3P3W, 400Amp Main Circuit Breaker, Indoor	EA	1.00	6,000.00	700.00	536.00	7,236.00	7,236.00	6,000.00	700.00	536.00	
POWER DISTRIBUTION PANEL	Main 400AF 208V/120V, 3P4W, 400Amp Main Circuit Breaker, Indoor	EA	1.00	6,700.00	700.00	536.00	7,936.00	7,936.00	6,700.00	700.00	536.00	
DRY-TYPE TRANSFORMERS	480-120/208V, 150KVA	SET	1.00	11,000.00	820.00	945.60	12,765.60	12,765.60	11,000.00	820.00	945.60	
LIGHTING FIXTURE	Type A1 Linear Light	EA	5.00	85.84	136.33	40.39	262.56	1,312.80	429.20	681.65	201.95	
LIGHTING FIXTURE	Type A1-EM Emergency Linear Light	EA	3.00	385.70	136.33	40.39	562.42	1,687.26	1,157.10	408.99	121.17	
LIGHTING FIXTURE	Type A2 Pendant Light	EA	6.00	220.98	136.33	40.39	397.70	2,386.20	1,325.88	817.98	242.34	
LIGHTING FIXTURE	Type EMWP1 Exit and Emergency Light	EA	1.00	128.45	65.45	15.51	209.41	209.41	128.45	65.45	15.51	
LIGHTING SUPPORT SYSTEM	TYPE A1/A2	SET	15.00	38.61	79.45	10.16	128.23	1,923.44	579.22	1,191.80	152.42	
SWITCH	nLIGHT LV Dimmer Switch	EA	2.00	301.79	56.93	5.76	364.48	728.96	603.58	113.85	11.53	
SWITCH	20Amp, 120/277V, 1Pole, GRS	EA	2.00	10.56	56.93	5.76	73.25	146.50	21.12	113.85	11.53	
RECEPTACLE	120V, 20A DUPLEX W/COVER	EA	8.00	18.19	71.16	7.65	97.00	775.98	145.55	569.25	61.18	
RECEPTACLE	120V, 15A DUPLEX W/COVER	EA	4.00	16.30	64.00	6.42	86.72	346.90	65.20	256.00	25.70	
RECEPTACLE	NEMA L6-20R Receptacle	EA	3.00	30.02	71.16	7.65	108.82	326.47	90.06	213.47	22.94	
RECEPTACLE	NEMA 10-50R Receptacle	EA	1.00	41.22	71.16	7.65	120.02	120.02	41.22	71.16	7.65	
JUNCTION BOX, NEMA-1	4" X 4" X 2" (1/2" & 3/4" KNOCK OUT)	EA	50.00	12.80	15.00	2.22	30.02	1,501.00	640.00	750.00	111.00	
DISCONNECT SWITCH	480V, 3x30 NEMA 1 (With Fuse)	EA	3.00	2,022.32	69.39	21.17	2,112.88	6,338.64	6,066.96	208.17	63.51	
DISCONNECT SWITCH	480V, 3x30 NEMA 1 (NON Fuse)	EA	2.00	172.42	69.39	21.17	262.98	525.96	344.84	138.78	42.34	
ELECTRICAL METALLIC TUBING (EMT)	3/4"	FT	600.00	1.80	2.99	0.37	5.16	3,096.00	1,080.00	1,794.00	222.00	
ELECTRICAL METALLIC TUBING (EMT)	1"	FT	150.00	2.25	3.42	0.43	6.10	915.00	337.50	513.00	64.50	
ELECTRICAL METALLIC TUBING (EMT)	2"	FT	30.00	5.23	4.84	0.73	10.80	324.00	156.90	145.20	21.90	
ELECTRICAL METALLIC TUBING (EMT)	2-1/2"	FT	80.00	7.96	9.11	1.26	18.33	1,466.40	636.80	728.80	100.80	
BUSHING	2"-1/2" LUG TYPE	EA	2.00	15.21	2.15	15.51	32.87	65.74	30.42	4.30	31.02	
ELECTRICAL METALLIC TUBING (EMT)	2" 90D ELBOW	EA	2.00	13.25	62.62	6.07	81.93	163.86	26.49	125.24	12.14	
ELECTRICAL METALLIC TUBING (EMT)	2-1/2" 90D ELBOW	EA	6.00	18.53	76.46	7.60	102.59	615.54	111.18	458.76	45.60	
CONDUIT SUPPORT SYSTEM	3/4"	SET	100.00	8.33	7.50	1.91	17.74	1,774.00	833.00	750.00	191.00	
CONDUIT SUPPORT SYSTEM	1"	SET	25.00	8.33	7.50	1.91	17.74	443.50	208.25	187.50	47.75	
CONDUIT SUPPORT SYSTEM	2"	SET	6.00	18.79	26.90	3.44	49.13	294.78	112.74	161.40	20.64	
CONDUIT SUPPORT SYSTEM	2-1/2"	SET	15.00	19.83	28.39	3.64	51.86	777.90	297.45	425.85	54.60	
UNISTRUT CHANNEL	1-5/8" x 1-5/8" 12G	FT	10.00	9.04	3.50	1.50	14.04	140.40	90.40	35.00	15.00	
CHANNEL BASE	6" x 6"	EA	4.00	29.00	5.50	2.50	37.00	148.00	116.00	22.00	10.00	
FLEXIBLE CONDUIT	3/4" LIQUIDTIGHT TYPE	FT	48.00	2.08	2.82	0.35	5.25	252.00	99.84	135.36	16.80	
FLEXIBLE CONDUIT	1" LIQUIDTIGHT TYPE	FT	18.00	3.53	3.71	0.50	7.74	139.32	63.54	66.78	9.00	
FLEXIBLE CONDUIT	2-1/2" LIQUIDTIGHT TYPE	FT	24.00	13.84	17.07	2.41	33.32	799.68	332.16	409.68	57.84	
FLEXIBLE CONNECTOR	3/4" LIQUIDTIGHT TYPE	EA	16.00	4.25	3.14	0.43	7.82	125.12	68.00	50.24	6.88	
FLEXIBLE CONNECTOR	1" LIQUIDTIGHT TYPE	EA	6.00	5.58	3.56	0.51	9.65	57.87	33.48	21.35	3.04	
FLEXIBLE CONNECTOR	2-1/2" LIQUIDTIGHT TYPE	EA	8.00	30.20	7.54	1.20	38.94	311.52	241.60	60.32	9.60	
PULL BOX	16" x 16" x 6" Deep Metal Pull Box	EA	4.00	174.03	108.99	22.64	305.66	1,222.65	696.12	435.96	90.57	
CABLE TRAY	9" Aluminum Ladder Cable Tray Straight	FT	36.00	28.30	20.23	3.88	52.41	1,886.76	1,018.80	728.28	139.68	
CABLE TRAY	9" Aluminum Horizontal 90-Degree Elbow	EA	1.00	253.21	190.50	35.50	479.21	479.21	253.21	190.50	35.50	
CABLE TRAY	9" Aluminum Vertical Elbow	EA	1.00	253.21	190.50	35.50	479.21	479.21	253.21	190.50	35.50	
CABLE TRAY Bonding Jumper	12" GROUND	EA	6.00	14.86	6.98	2.06	23.90	143.40	89.16	41.88	12.36	
CABLE TRAY SUPPORT SYSTEM	9" Width including beam clamp, square washer, unistrut, 2 rods, etc	SET	8.00	133.09	38.92	4.09	176.10	1,408.80	1,064.72	311.36	32.72	
CABLE TRAY COVER	9" Tray: Partial Cover Basis	FT	6.00	11.78	10.99	1.98	24.75	148.51	70.69	65.96	11.86	
CABLE HOLDER	Trefoil Cable Cleat	EA	35.00	98.27	22.12	9.63	130.02	4,550.74	3,439.45	774.20	337.09	
Multi Conductor (THHN/THWN-2) ~ Stranded	#12AWG (2C+ G) Tray-Rated Cable	FT	1,110.00	1.20	0.99	0.22	2.41	2,673.73	1,332.00	1,097.53	244.20	
Multi Conductor (THHN/THWN-2) ~ Stranded	#12AWG (3C+ G) Tray-Rated Cable	FT	630.00	2.34	0.99	0.33	3.66	2,305.80	1,474.20	623.70	207.90	
Multi Conductor (THHN/THWN-2) ~ Stranded	#8AWG (2C+ G) Tray-Rated Cable	FT	100.00	1.55	1.79	0.33	3.67	367.40	155.00	179.00	33.40	
Multi Conductor (THHN/THWN-2) ~ Stranded	#8AWG (3C+ G) Tray-Rated Cable	FT	100.00	4.58	1.53	0.61	6.72	672.00	458.00	153.00	61.00	
Multi Conductor (THHN/THWN-2) ~ Stranded	#6AWG (2C+ G) Tray-Rated Cable	FT	100.00	1.88	2.57	0.45	4.90	489.50	188.00	257.00	44.50	
Multi Conductor (THHN/THWN-2) ~ Stranded	#6AWG (3C+ G) Tray-Rated Cable	FT	100.00	6.09	1.68	0.78	8.55	855.00	609.00	168.00	78.00	
SINGLE Conductor (THHN/THWN-2) ~ Stranded	AWG#12	FT	760.00	0.71	0.95	0.17	1.83	1,390.80	539.60	722.00	129.20	
SINGLE Conductor (THHN/THWN-2) ~ Stranded	AWG#4 GROUND	FT	145.00	2.37	1.27	0.36	4.00	580.00	343.65	184.15	52.20	
SINGLE Conductor (THHN/THWN-2) ~ Stranded	AWG#1/0 GROUND	FT	50.00	4.65	1.90	0.68	7.23	361.50	232.50	95.00	34.00	
SINGLE Conductor (THHN/THWN-2) ~ Stranded	AWG#4/0	FT	200.00	8.58	4.47	1.40	14.45	2,890.00	1,716.00	894.00	280.00	
SINGLE Conductor (THHN/THWN-2) ~ Stranded	250 KCMIL	FT	360.00	10.98	5.60	1.94	18.52	6,667.20	3,952.80	2,016.00	698.40	
CONNECTION AND TERMINATION	AWG#12	EA	36.00	0.76	3.03	0.30	4.09	147.20	27.32	109.08	10.80	
CONNECTION AND TERMINATION	AWG#4 GROUND	EA	4.00	5.38	5.82	0.90	12.10	48.39	21.52	23.28	3.60	
CONNECTION AND TERMINATION	AWG#1/0 GROUND	EA	4.00	7.27	7.85	1.21	16.34	65.34	29.08	31.42	4.84	
CONNECTION AND TERMINATION	AWG#4/0	EA	16.00	10.02	16.93	2.16	29.11	465.74	160.34	270.85	34.56	
CONNECTION AND TERMINATION	250 KCMIL	EA	12.00	11.03	17.35	2.27	30.66	367.88	132.40	208.24	27.24	
PVC CONDUIT	1" SCH 40	FT	70.00	1.48	2.05	0.30	3.83	268.10	103.60	143.50	21.00	
Bonding Jumper	BEAN BONDING	EA	3.00	37.25	74.75	9.64	121.64	364.91	111.74	224.25	28.82	
SINGLE Conductor (THHN/THWN-2) ~ Stranded	AWG#4/0 BC WIRE	FT	50.00	8.58	4.47	1.40	14.45	722.50	429.00	223.50	70.00	
SINGLE Conductor (THHN/THWN-2) ~ Stranded	AWG#1/0 GROUND	FT	15.00	4.65	1.90	0.68	7.23	108.45	69.75	28.50	10.20	
[Sub Total]								90,308.50	59,184.99	24,305.80	6,817.70	
0102. INSTRUMENT WORK												
ELECTRICAL METALLIC TUBING (EMT)	3/4"	FT	160.00	1.80	2.99	0.37	5.16	825.60	288.00	478.40	59.20	
ELECTRICAL METALLIC TUBING (EMT)	1-1/4"	FT	120.00	3.65	3.70	0.54	7.89	946.80	438.00	444.00	64.80	
UNISTRUT CHANNEL	1-5/8" x 1-5/8" 12G	FT	10.00	9.04	3.50	1.50	14.04	140.40	90.40	35.00	15.00	
FLEXIBLE CONDUIT	3/4" LIQUIDTIGHT TYPE	FT	60.00	2.08	2.82	0.35	5.25	315.00	124.80	169.20	21.00	
FLEXIBLE CONDUIT	1/2" LIQUIDTIGHT TYPE	FT	12.00	1.60	2.56	0.32	4.48	53.76	19.20	30.72	3.84	
FLEXIBLE CONNECTOR	3/4" LIQUIDTIGHT TYPE	EA	20.00	3.25	3.14	0.43	6.82	136.40	65.00	62.80	8.60	
FLEXIBLE CONNECTOR	1/2" LIQUIDTIGHT TYPE	EA	4.00	3.25	2.24	0.38	5.87	23.48	13.00	8.96	1.52	
CONDUIT SUPPORT SYSTEM	3/4"	SET	50.00	8.33	7.50	1.91	17.74	887.00	416.50	375.00		