



5341 Perimeter Parkway Ct. Montgomery AL 36116 Email : tkelectricoffice@gmail.com

QUOTATION

1 SERVICE PROVIDER		8 PO NUMBER / DATE OF QUOTATION	
TK ELECTRIC LLC 765 Us Highway 80, Eden, GA 31307		TKM101027	February 17, 2026
2 CONSIGNEE		9 REMARKS	
HMGMA Bryan County Megasite, Ellabell, GA 31308			
3 CONTACT			
Mr. Hyungjoon Jang Hyungjoon.Jang@hmgma.com			
4 PROJECT NAME	5 SERVICE PERIOD		
800_POD INSPECTION	2026		
6 CARRIER	7 SERVICE LOCATION	10 PROJECT MANAGER	11 SAFETY MANAGER
TK ELECTRIC LLC	Ellabell ,GA	Park, Junggu	CHRIS, HILGER
12 PROJECT NAME & DESCRIPTION		13 QTY	14 UNIT
■ POD INSPECTION			
☐ POWER DISTRIBUTION PLAN		1.0	LOT
☐ GROUNDING PLAN		1.0	LOT
☐ MECHANICAL POWER PLAN		1.0	LOT
☐ LIGHTING PLAN		1.0	LOT
CONDITIONS AND TERMS		MATERIALS	
		\$ 244,974.04	
		LABOR	
		\$ 185,226.87	
		EXPENSE	
		\$ 25,811.78	
		EQUIPMENT	
\$ 9,300.00			
SUB. TOTAL		\$ 465,312.69	
		SAFETY / MANAGEMENT	
		\$ 23,712.66	
		\$ 489,025.35	
APPROVED BY :		G. TOTAL	
		\$ 489,000.00	

DATE : February 17, 2026

TAE K. KIM / PRESIDENT

[B.O.Q]

SUBCONTRACTOR : TK ELECTRIC LLC

[illegible]

[B.O.Q]

PROJECT :POD INSPECTION
CONSTRUCTION PERIOD : '2026
SUBCONTRACTOR : TK ELECTRIC LLC

품 명 DESCRIPTION OF WORK		규 격 SPECIFICATION	단 위 UNIT	Bill of Quantity									비 고 REMARKS
				수 량 Q'ty	ITEM PRICE PER ITEM			단 가 Unit Price	금 액 Amount	ITEM PRICE PER CLASSIFICATION			
					MATERIAL	LABOR	EXPENSE			MATERIAL	LABOR	EXPENSE	
■POD INSPECTION													
1.POD INSPECTION													
□ POWER DIST RIBUTION PLAN													
NEW PANEL(PO-8001)	600 AMP 480/277V NEMA1	EA	1	12,145.00	680.00	769.50	13,594.50	13,594.50	12,145.00	680.00	769.50		
T TRANSFORMER (TRO-8001)	45KVA 480:208/120V)	EA	1	3,887.00	800.00	281.22	4,968.22	4,968.22	3,887.00	800.00	281.22		
NEW PANEL(PO-LDP)	125 AMP 208/120V 3PH,4W 42CKT	EA	1	1,600.00	340.00	116.40	2,056.40	2,056.40	1,600.00	340.00	116.40		
PVC CONDUIT , SCHEDULE 40	4"	FT	2000	8.11	11.00	1.15	20.26	40,519.30	16,225.76	22,000.00	2,293.54		
PVC CONDUIT , SCHEDULE 40 ELBOW	4"	FT	8	21.77	15.00	2.21	38.97	311.76	174.12	120.00	17.64		
MANHOLE (CONCRETE TYPE)	5'W x 5'H x 5'D	EA	5	7,200.00	5,800.00	780.00	13,780.00	68,900.00	36,000.00	29,000.00	3,900.00		
Asphalt cutting, Excavate, Concrete back filling, Asphalt finish	3'W x 4'H (Asphalt cutting) 110ft	FT	1000	16.40	9.80	1.57	27.77	27,772.00	16,400.00	9,800.00	1,572.00		
Single Conductor (THHN/THWN) – Stranded	AWG #350	EA	8800	9.84	5.72	0.93	16.49	145,143.68	86,592.00	50,336.00	8,215.68		
Single Conductor (THHN/THWN) – Stranded	AWG #1/0 (GROUNDING)	FT	2200	3.34	1.80	0.31	5.45	11,995.80	7,356.80	3,960.00	679.00		
LIQUIDTIGHT FLEXIBLE CONDUIT	1-1/2"	EA	6	6.18	8.54	0.88	15.60	93.58	37.06	51.23	5.29		
CONDUIT HANGER SUPPORT	1-1/2"	FT	4	12.38	14.66	1.62	28.66	114.64	49.52	58.64	6.48		
ELECTRICAL METALLIC TUBING (EMT)+ FITTING	1-1/2"	EA	10	3.10	4.27	0.44	7.81	78.13	31.02	42.69	4.42		
Single Conductor (THHN/THWN-2) – Stranded	AWG#4	FT	60	2.03	1.45	0.21	3.69	221.19	121.73	86.94	12.52		
Single Conductor (THHN/THWN-2) – Stranded	AWG#8(GROUNDING)	EA	20	0.59	0.91	0.09	1.58	31.67	11.77	18.11	1.79		
Single Conductor (THHN/THWN-2) – Stranded	AWG#1	FT	80	2.33	1.64	0.24	4.21	336.65	186.40	131.20	19.05		
Single Conductor (THHN/THWN-2) – Stranded	AWG#6(GROUNDING)	EA	20	0.87	1.04	0.11	2.02	40.49	17.40	20.80	2.29		
LIQUIDTIGHT FLEXIBLE CONDUIT	2"	FT	6	6.18	8.54	0.88	15.60	93.61	37.08	51.24	5.29		
ELECTRICAL METALLIC TUBING (EMT)+ FITTING	2"	EA	10	3.63	4.84	0.51	8.98	89.79	36.33	48.38	5.08		
CONDUIT HANGER SUPPORT	2"	FT	4	14.38	16.66	1.86	32.90	131.60	57.52	66.64	7.44		
PVC CONDUIT , SCHEDULE 40	1" (TR Ground)	EA	30	0.76	3.02	0.23	4.01	120.31	22.77	90.73	6.81		
Single Conductor (THHN/THWN-2) – Stranded	AWG#6(TR GROUNDING)	FT	30	0.87	1.04	0.11	2.02	60.73	26.10	31.20	3.43		
CONNECTION AND TERMINATION	#350 Kcmil COMPRESSION TYPE	EA	16	21.66	19.71	2.48	43.85	701.62	346.54	315.37	39.71		
CONNECTION AND TERMINATION	AWG#1/0 COMPRESSION TYPE	FT	4	9.23	11.68	1.25	22.17	88.65	36.91	46.73	5.01		
CONNECTION AND TERMINATION	AWG#1 COMPRESSION TYPE	EA	8	7.27	7.85	0.91	16.03	128.21	58.16	62.80	7.25		
CONNECTION AND TERMINATION	AWG#4 COMPRESSION TYPE	FT	6	5.38	5.82	0.67	11.87	71.21	32.27	34.91	4.03		
CONNECTION AND TERMINATION	AWG#6 COMPRESSION TYPE	EA	2	2.67	4.53	0.43	7.64	15.26	5.34	9.06	0.86		
CONNECTION AND TERMINATION	AWG#8 COMPRESSION TYPE	FT	4	1.58	4.09	0.34	6.02	24.06	6.33	16.37	1.36		
ALUMINUM CABLE TRAY (LADDER TYPE)	24"Width, 4"height, 9"rung spacing	EA	170	19.05	19.23	2.30	40.57	6,897.62	3,238.09	3,269.10	390.43		
ALUMINUM HORIZONTAL ELBOW (LADDER TYPE)	24"Width, 4"height, 9"rung spacing	FT	2	182.00	42.15	13.45	237.60	475.19	364.00	84.30	26.89		
ALUMINUM VERTICAL ELBOW (LADDER TYPE)	24"Width, 4"height, 9"rung spacing	EA	1	195.00	44.25	14.36	253.61	253.60	195.00	44.25	14.35		
CABLE TRAY SUPPORT	24" Width including beam clamp, square washer, unistrut, 2 rods(length:4ft~8ft, dia: 9/16"), etc	FT	29	78.09	51.90	7.80	137.79	3,995.89	2,264.61	1,505.10	226.18		
CABLE TRAY BONDING JUMPER	12"	EA	22	34.97	14.23	2.95	52.15	1,147.33	769.31	313.08	64.94		
[Sub Total]								330,472.69	188,331.94	123,434.87	18,705.88		
□ GROUNDING PLAN													
Single Conductor (THHN/THWN) – BARE	AWG#4/0(GROUNDING)	SET	540	5.27	4.47	0.58	10.33	5,576.45	2,844.97	2,415.84	315.64		
Excavation /w backfill	W8" x H24" MESH	FT	460	17.20	8.50	1.54	27.24	12,531.32	7,912.00	3,910.00	709.32		
PVC CONDUIT , SCHEDULE 40	1"	EA	40	1.48	2.05	0.21	3.73	149.36	59.03	81.88	8.45		
COPPER ROD	3/4 " X 10 '	EA	8	29.19	256.16	17.12	302.47	2,419.78	233.52	2,049.30	136.96		
EXOTHERMIC WELDING CONNECTION (COLUMN)	Mold , Ultra Shot , #90 , Weld to Column	FT	4	13.58	14.23	1.67	29.48	117.90	54.31	56.92	6.67		
EXOTHERMIC WELDING CONNECTION (GROUND ROD)	Mold , Ultra Shot , #90 , Weld to Rod	EA	8	13.58	14.23	1.67	29.48	235.82	108.63	113.85	13.34		
							-	-	-	-	-		
[Sub Total]								21,030.63	11,212.46	8,627.79	1,190.38		

[B.O.Q]

PROJECT :POD INSPECTION

CONSTRUCTION PERIOD : '2026

SUBCONTRACTOR : TK ELECTRIC LLC

품 명 DESCRIPTION OF WORK		규 격 SPECIFICATION	단 위 UNIT	Bill of Quantity								비 고 REMARKS	
				수 량 Q'ty	ITEM PRICE PER ITEM			단 가 Unit Price	금 액 Amount	ITEM PRICE PER CLASSIFICATION			
					MATERIAL	LABOR	EXPENSE			MATERIAL	LABOR		EXPENSE
☐ MECHANICAL POWER PLAN													
CONDUIT HANGER SUPPORT	2-1/2"	SET	15	14.38	15.66	1.80	31.84	477.63	215.70	234.90	27.03		
CONDUIT HANGER SUPPORT	3/4"	SET	111	12.38	14.66	1.62	28.66	3,181.52	1,374.18	1,627.26	180.08		
CONNECTION AND TERMINATION	AWG#3/0 COMPRESSION TYPE	EA	18	11.68	9.49	1.27	22.44	403.94	210.31	170.77	22.86		
CONNECTION AND TERMINATION	AWG#6 COMPRESSION TYPE	FT	6	2.67	4.53	0.43	7.63	45.79	16.02	27.18	2.59		
CONNECTION AND TERMINATION	AWG#10 COMPRESSION TYPE	EA	132	0.76	3.02	0.23	4.01	528.89	100.32	398.64	29.93		
DISCONNECT SWITCH	480V , 30 NEMA 1 (Without Fuse)	FT	6	142.85	77.63	13.23	233.71	1,402.24	857.12	465.75	79.37		
ELECTRICAL METALLIC TUBING (EMT) ELBOW	2-1/2"	EA	3	22.50	86.85	6.56	115.91	347.73	67.50	260.55	19.68		
ELECTRICAL METALLIC TUBING (EMT)+ FITTING	2-1/2"	FT	90	5.52	9.11	0.88	15.51	1,395.67	496.95	819.72	79.00		
ELECTRICAL METALLIC TUBING (EMT)+ FITTING	3/4"	FT	540	1.16	2.99	0.25	4.40	2,375.46	626.40	1,614.60	134.46		
LIQUIDTIGHT FLEXIBLE CONDUIT	3/4"	FT	72	1.58	2.82	0.26	4.66	335.80	113.76	203.04	19.00		
LIQUIDTIGHT FLEXIBLE CONDUIT CONNECTOR	3/4"	EA	24	4.25	3.14	0.44	7.83	188.00	102.00	75.36	10.64		
Multi Conductor (THHN/THWN-2) – Stranded	(3PH+ 1N+ GROUNDING) AWG#10	FT	2130	1.48	1.14	0.16	2.78	5,910.93	3,152.40	2,423.95	334.58		
Single Conductor (THHN/THWN-2) – Stranded	AWG#3/0	FT	1620	4.47	0.97	0.33	5.77	9,351.10	7,247.53	1,574.27	529.30		
Single Conductor (THHN/THWN-2) – Stranded	AWG#6(GROUNDING)	FT	540	0.87	1.04	0.11	2.02	1,093.28	469.80	561.60	61.88		
[Sub Total]								27,037.98	15,049.99	10,457.59	1,530.40		
☐ LIGHTING PLAN													
LED FLOOD LIGHTING	LED 95W	EA	36	308.00	225.96	32.04	566.00	20,376.04	11,088.00	8,134.68	1,153.36		
LED LIGHTING Canopy	LED 20W	EA	14	90.00	129.12	13.15	232.27	3,251.76	1,260.00	1,807.70	184.06		
WALL MOUNTED	LED 80W	EA	4	330.00	250.00	34.80	614.80	2,459.20	1,320.00	1,000.00	139.20		
EMERGENCY EXIT LED SIGN	LED 2W	EA	12	103.53	64.50	10.08	178.11	2,137.34	1,242.36	774.00	120.98		
CONDUIT HANGER SUPPORT	3/4"	SET	375	12.38	14.66	1.62	28.66	10,748.40	4,642.50	5,497.50	608.40		
CONNECTION AND TERMINATION	AWG#10	EA	288	3.02	2.02	0.30	5.35	1,540.88	871.05	582.61	87.22		
CONNECTION AND TERMINATION	AWG#12(GROUNDING)	EA	144	2.98	2.00	0.30	5.28	760.14	429.12	288.00	43.02		
ELECTRICAL METALLIC TUBING (EMT)+ FITTING	3/4"	FT	2240	1.16	2.99	0.25	4.40	9,853.76	2,598.40	6,697.60	557.76		
JUNCTION BOX, NEMA-1	4" X 4" X 2" (1/2" & 3/4" KNOCK OUT) pigtail / wire connector / blank cover / label	EA	83	8.90	35.80	2.68	47.38	3,932.70	738.70	2,971.40	222.60		
Single Conductor (THHN/THWN-2) – Stranded	AWG#10	FT	4600	0.39	0.97	0.08	1.44	6,631.36	1,794.00	4,462.00	375.36		
Single Conductor (THHN/THWN-2) – Stranded	AWG#12(GROUNDING)	FT	2300	0.29	0.95	0.07	1.31	3,023.12	667.00	2,185.00	171.12		
WALL SWITCH	120-277V , SINGLE POLE	EA	2	10.56	56.93	4.05	71.53	143.06	21.12	113.85	8.09		
[Sub Total]								64,857.76	26,672.25	34,514.34	3,671.17		
☐ RECEPTACLE PLAN													
CONDUIT HANGER SUPPORT	3/4"	SET	117	12.38	14.66	1.62	28.66	3,353.50	1,448.46	1,715.22	189.82		
ELECTRICAL METALLIC TUBING (EMT)+ FITTING	3/4"	FT	720	1.16	2.99	0.25	4.40	3,167.28	835.20	2,152.80	179.28		
JUNCTION BOX, NEMA-1	4" X 4" X 2" (1/2" & 3/4" KNOCK OUT) pigtail / wire connector / blank cover / label	EA	24	8.90	35.80	2.68	47.38	1,137.16	213.60	859.20	64.36		
RECEPTACLE	120V , 20A DUPLEX.	EA	12	15.38	62.67	4.68	82.73	992.79	184.56	752.04	56.19		
Receptacle Metal Cover	1Gang 4" X 4"	EA	12	2.54	2.11	0.28	4.93	59.14	30.48	25.32	3.34		
Single Conductor (THHN/THWN-2) – Stranded	AWG#10	FT	1860	0.39	0.97	0.08	1.44	2,681.37	725.40	1,804.20	151.77		
Single Conductor (THHN/THWN-2) – Stranded	AWG#12(GROUNDING)	FT	930	0.29	0.95	0.07	1.31	1,222.39	269.70	883.50	69.19		
[Sub Total]								12,613.63	3,707.40	8,192.28	713.95		
☐ RENTAL EQUIPMENT													
SCISSRO LIFT	24'~26'	EA	3	-	-	1,200.00	1,200.00	3,600.00	-	-	3,600.00		
BOOM LIFT	27'	EA	1	-	-	1,900.00	1,900.00	1,900.00	-	-	1,900.00		
EXCAVATOR	18000lb	EA	1	-	-	3,800.00	3,800.00	3,800.00	-	-	3,800.00		
							-	-	-	-	-		
[Sub Total]								9,300.00	-	-	9,300.00		
[Total]													

No.	Description	Specification	Units	Calculation		Quantity
				dist.	piece	
■POD INSPECTION						
1.POD INSPECTION						
□ POWER DISTRIBUTION PLAN	NEW PANEL(PO-8001)	600 AMP 480/277V NEMA1	EA	1	1	1
	TRANSFORMER (TRO-8001)	45KVA 480:208/120V NEMA1	EA	1	1	1
	NEW PANEL(PO-LDP)	125 AMP 208/120V 3PH,4W 42CKT	FT	1	1	1
	PVC CONDUIT, SCHEDULE 40	4"	FT	1000	2	2000
	PVC CONDUIT, SCHEDULE 40 ELBOW	4"	EA	8	1	8
	MANHOLE (CONCRETE TYPE)	5'W x 5'H x 5'D	EA	5	1	5
	Asphalt cutting, Excavate, Concrete back filling, Asphalt finish	3'W x 4'H (Asphalt cutting) 110ft	FT	1000	1	1000
	Single Conductor (THHN/THWN) - Stranded	AWG #350	FT	1100	8	8800
	Single Conductor (THHN/THWN) - Stranded	AWG #1/0 (GROUNDING)	FT	1100	2	2200
	LIQUIDTIGHT FLEXIBLE CONDUIT	1-1/2"	FT	6	1	6
	CONDUIT HANGER SUPPORT	1-1/2"	SET	4	1	4
	ELECTRICAL METALLIC TUBING (EMT)+FITTING	1-1/2"	FT	10	1	10
	Single Conductor (THHN/THWN-2) - Stranded	AWG#4	FT	20	3	60
	Single Conductor (THHN/THWN-2) - Stranded	AWG#8(GROUNDING)	FT	20	1	20
	Single Conductor (THHN/THWN-2) - Stranded	AWG#1	FT	20	4	80
	Single Conductor (THHN/THWN-2) - Stranded	AWG#6(GROUNDING)	FT	20	1	20
	LIQUIDTIGHT FLEXIBLE CONDUIT	2"	FT	6	1	6
	ELECTRICAL METALLIC TUBING (EMT)+FITTING	2"	FT	10	1	10
	CONDUIT HANGER SUPPORT	2"	SET	4	1	4
	PVC CONDUIT, SCHEDULE 40	1" (TR Ground)	FT	30	1	30
	Single Conductor (THHN/THWN-2) - Stranded	AWG#6(TR GROUNDING)	FT	30	1	30
	CONNECTION AND TERMINATION	#350 Kcmil COMPRESSION TYPE	EA	8	2	16
	CONNECTION AND TERMINATION	AWG#1/0 COMPRESSION TYPE	EA	2	2	4
	CONNECTION AND TERMINATION	AWG#1 COMPRESSION TYPE	EA	4	2	8
	CONNECTION AND TERMINATION	AWG#4 COMPRESSION TYPE	EA	3	2	6
	CONNECTION AND TERMINATION	AWG#6 COMPRESSION TYPE	EA	2	1	2
	CONNECTION AND TERMINATION	AWG#8 COMPRESSION TYPE	EA	4	1	4
	ALUMINUM CABLE TRAY (LADDER TYPE)	24"Width, 4"height, 9"rung spacing	FT	170	1	170
	ALUMINUM HORIZONTAL ELBOW (LADDER TYPE)	24"Width, 4"height, 9"rung spacing	EA	2	1	2
	ALUMINUM VERTICAL ELBOW (LADDER TYPE)	24"Width, 4"height, 9"rung spacing	EA	1	1	1
	CABLE TRAY SUPPORT	24" Width including beam clamp, square washer, unistrut, 2 rods(length:4ft~8ft, dia: 9/16"), etc	SET	29	1	29
	CABLE TRAY BONDING JUMPER	12"	EA	22	1	22
						0
□ GROUNDING PLAN						0
	Single Conductor (THHN/THWN) - BARE	AWG#4/0(GROUNDING)	FT	540	1	540
	Excavation /w backfill	W8" x H24" MESH	FT	460	1	460
	PVC CONDUIT, SCHEDULE 40	1"	FT	40	1	40
	COPPER ROD	3/4 " X 10 '	EA	8	1	8
	EXOTHEMIC WELDING CONNECTION (COLUMN)	Mold , Ultra Shot , #90 , Weld to Column	EA	4	1	4
	EXOTHEMIC WELDING CONNECTION (GROUND ROD)	Mold , Ultra Shot , #90 , Weld to Rod	EA	8	1	8

No.	Description	Specification	Units	Calculation		Quantity
				dist.	piece	
				0	1	0

No.	Description	Specification	Units	Calculation		Quantity
				dist.	piece	
☐ MECHANICAL POWER PLAN						0
☐FORM_PO-8001				0	1	0
☐DO1 (SHUTTER)	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	40	1	40
	LIQUIDTIGHT FLEXIBLE CONDUIT	3/4"	FT	12	1	12
	CONDUIT HANGER SUPPORT	3/4"	EA	11	1	11
	Multi Conductor (THHN/THWN-2) - Stranded	(3PH+1N+GROUNDING) AWG#10	FT	80	1	80
	CONNECTION AND TERMINATION	AWG#10 COMPRESSION TYPE	EA	4	4	16
	DISCONNECT SWITCH	480V, 30 NEMA 1 (Without Fuse)	EA	1	1	1
☐DO2 (SHUTTER)	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	70	1	70
	LIQUIDTIGHT FLEXIBLE CONDUIT	3/4"	FT	12	1	12
	CONDUIT HANGER SUPPORT	3/4"	EA	16	1	16
	Multi Conductor (THHN/THWN-2) - Stranded	(3PH+1N+GROUNDING) AWG#10	FT	110	1	110
	CONNECTION AND TERMINATION	AWG#10 COMPRESSION TYPE	EA	4	4	16
	DISCONNECT SWITCH	480V, 30 NEMA 1 (Without Fuse)	EA	1	1	1
☐DO3 (SHUTTER)	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	100	1	100
	LIQUIDTIGHT FLEXIBLE CONDUIT	3/4"	FT	12	1	12
	CONDUIT HANGER SUPPORT	3/4"	EA	21	1	21
	Multi Conductor (THHN/THWN-2) - Stranded	(3PH+1N+GROUNDING) AWG#10	FT	140	1	140
	CONNECTION AND TERMINATION	AWG#10 COMPRESSION TYPE	EA	4	4	16
	DISCONNECT SWITCH	480V, 30 NEMA 1 (Without Fuse)	EA	1	1	1
☐DO4 (SHUTTER)	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	50	1	50
	LIQUIDTIGHT FLEXIBLE CONDUIT	3/4"	FT	12	1	12
	CONDUIT HANGER SUPPORT	3/4"	EA	11	1	11
	Multi Conductor (THHN/THWN-2) - Stranded	(3PH+1N+GROUNDING) AWG#10	FT	160	1	160
	CONNECTION AND TERMINATION	AWG#10 COMPRESSION TYPE	EA	4	4	16
	DISCONNECT SWITCH	480V, 30 NEMA 1 (Without Fuse)	EA	1	1	1
☐DO5 (SHUTTER)	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	50	1	50
	LIQUIDTIGHT FLEXIBLE CONDUIT	3/4"	FT	12	1	12
	CONDUIT HANGER SUPPORT	3/4"	EA	11	1	11
	Multi Conductor (THHN/THWN-2) - Stranded	(3PH+1N+GROUNDING) AWG#10	FT	190	1	190
	CONNECTION AND TERMINATION	AWG#10 COMPRESSION TYPE	EA	4	4	16
	DISCONNECT SWITCH	480V, 30 NEMA 1 (Without Fuse)	EA	1	1	1
☐DO6 (SHUTTER)	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	50	1	50
	LIQUIDTIGHT FLEXIBLE CONDUIT	3/4"	FT	12	1	12
	CONDUIT HANGER SUPPORT	3/4"	EA	11	1	11
	Multi Conductor (THHN/THWN-2) - Stranded	(3PH+1N+GROUNDING) AWG#10	FT	220	1	220
	CONNECTION AND TERMINATION	AWG#10 COMPRESSION TYPE	EA	4	4	16
	DISCONNECT SWITCH	480V, 30 NEMA 1 (Without Fuse)	EA	1	1	1
☐PLC1 CONTROL PANEL-1	ELECTRICAL METALLIC TUBING (EMT)+FITTING	2-1/2"	FT	30	1	30
	ELECTRICAL METALLIC TUBING (EMT) ELBOW	2-1/2"	EA	1	1	1
	CONDUIT HANGER SUPPORT	2-1/2"	EA	5	1	5
	Single Conductor (THHN/THWN-2) - Stranded	AWG#3/0	FT	150	3	450
	Single Conductor (THHN/THWN-2) - Stranded	AWG#6(GROUNDING)	FT	150	1	150
	CONNECTION AND TERMINATION	AWG#3/0 COMPRESSION TYPE	EA	3	2	6

No.	Description	Specification	Units	Calculation		Quantity
				dist.	piece	
☐PLC2 CONTROL PANEL-2	CONNECTION AND TERMINATION	AWG#6 COMPRESSION TYPE	EA	1	2	2
	ELECTRICAL METALLIC TUBING (EMT)+FITTING	2-1/2"	FT	30	1	30
	ELECTRICAL METALLIC TUBING (EMT) ELBOW	2-1/2"	EA	1	1	1
	CONDUIT HANGER SUPPORT	2-1/2"	EA	5	1	5
	Single Conductor (THHN/THWN-2) - Stranded	AWG#3/0	FT	180	3	540
	Single Conductor (THHN/THWN-2) - Stranded	AWG#6(GROUNDING)	FT	180	1	180
	CONNECTION AND TERMINATION	AWG#3/0 COMPRESSION TYPE	EA	3	2	6
☐PLC3 CONTROL PANEL-3	CONNECTION AND TERMINATION	AWG#6 COMPRESSION TYPE	EA	1	2	2
	ELECTRICAL METALLIC TUBING (EMT)+FITTING	2-1/2"	FT	30	1	30
	ELECTRICAL METALLIC TUBING (EMT) ELBOW	2-1/2"	EA	1	1	1
	CONDUIT HANGER SUPPORT	2-1/2"	EA	5	1	5
	Single Conductor (THHN/THWN-2) - Stranded	AWG#3/0	FT	210	3	630
	Single Conductor (THHN/THWN-2) - Stranded	AWG#6(GROUNDING)	FT	210	1	210
	CONNECTION AND TERMINATION	AWG#3/0 COMPRESSION TYPE	EA	3	2	6
☐FROM_RO-8001	CONNECTION AND TERMINATION	AWG#6 COMPRESSION TYPE	EA	1	2	2
				0	1	0
				0	1	0
☐PC1_PC CONTROL PANEL-1	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	30	1	30
	CONDUIT HANGER SUPPORT	3/4"	EA	5	1	5
	Multi Conductor (THHN/THWN-2) - Stranded	(3PH+1N+GROUNDING) AWG#10	FT	130	1	130
	CONNECTION AND TERMINATION	AWG#10 COMPRESSION TYPE	EA	2	2	4
	CONNECTION AND TERMINATION	AWG#10 COMPRESSION TYPE	EA	1	2	2
☐PC2_PC CONTROL PANEL-2	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	30	1	30
	CONDUIT HANGER SUPPORT	3/4"	EA	5	1	5
	Multi Conductor (THHN/THWN-2) - Stranded	(3PH+1N+GROUNDING) AWG#10	FT	160	2	320
	CONNECTION AND TERMINATION	AWG#10 COMPRESSION TYPE	EA	2	2	4
	CONNECTION AND TERMINATION	AWG#10 COMPRESSION TYPE	EA	1	2	2
☐PC3_PC CONTROL PANEL-3	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	30	1	30
	CONDUIT HANGER SUPPORT	3/4"	EA	5	1	5
	Multi Conductor (THHN/THWN-2) - Stranded	(3PH+1N+GROUNDING) AWG#10	FT	170	1	170
	CONNECTION AND TERMINATION	AWG#10 COMPRESSION TYPE	EA	2	2	4
	CONNECTION AND TERMINATION	AWG#10 COMPRESSION TYPE	EA	1	2	2
☐PC4_PC CONTROL PANEL-4	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	30	1	30
	CONDUIT HANGER SUPPORT	3/4"	EA	5	1	5
	Multi Conductor (THHN/THWN-2) - Stranded	(3PH+1N+GROUNDING) AWG#10	FT	190	1	190
	CONNECTION AND TERMINATION	AWG#10 COMPRESSION TYPE	EA	2	2	4
	CONNECTION AND TERMINATION	AWG#10 COMPRESSION TYPE	EA	1	2	2
☐PC5_PC CONTROL PANEL-5	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	30	1	30
	CONDUIT HANGER SUPPORT	3/4"	EA	5	1	5
	Multi Conductor (THHN/THWN-2) - Stranded	(3PH+1N+GROUNDING) AWG#10	FT	200	1	200
	CONNECTION AND TERMINATION	AWG#10 COMPRESSION TYPE	EA	2	2	4
	CONNECTION AND TERMINATION	AWG#10 COMPRESSION TYPE	EA	1	2	2
☐PC6_PC CONTROL PANEL-6	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	30	1	30
	CONDUIT HANGER SUPPORT	3/4"	EA	5	1	5

No.	Description	Specification	Units	Calculation		Quantity
				dist.	piece	
	Multi Conductor (THHN/THWN-2) - Stranded	(3PH+1N+GROUNDING) AWG#10	FT	220	1	220
	CONNECTION AND TERMINATION	AWG#10 COMPRESSION TYPE	EA	2	2	4
	CONNECTION AND TERMINATION	AWG#10 COMPRESSION TYPE	EA	1	2	2
				0	1	0

No.	Description	Specification	Units	Calculation		Quantity
				dist.	piece	
☐ LIGHTING PLAN						
☐CIRCUIT-L1	LED FLOOD LIGHTING	LED 95W	EA	18	1	18
	EMERGENCY EXIT LED SIGN	LED 2W	EA	6	1	6
	WALL MOUNTED	LED 80W	EA	2	1	2
	LED LIGHTING Canopy	LED 20W	EA	14	1	14
	WALL SWITCH	120-277V, SINGLE POLE	EA	2	1	2
	Single Conductor (THHN/THWN-2) - Stranded	AWG#10	FT	1120	2	2240
	Single Conductor (THHN/THWN-2) - Stranded	AWG#12(GROUNDING)	FT	1120	1	1120
	CONNECTION AND TERMINATION	AWG#10	EA	80	2	160
	CONNECTION AND TERMINATION	AWG#12(GROUNDING)	EA	80	1	80
	JUNCTION BOX, NEMA-1	4" X 4" X 2" (1/2" & 3/4" KNOCK OUT) pigtail / wire connector / blank cover / label	EA	46	1	46
	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	1100	1	1100
	CONDUIT HANGER SUPPORT	3/4"	EA	184	1	184
☐CIRCUIT-L2	LED FLOOD LIGHTING	LED 95W	EA	18	1	18
	EMERGENCY EXIT LED SIGN	LED 2W	EA	6	1	6
	WALL MOUNTED	LED 80W	EA	2	1	2
	Single Conductor (THHN/THWN-2) - Stranded	AWG#10	FT	790	2	1580
	Single Conductor (THHN/THWN-2) - Stranded	AWG#12(GROUNDING)	FT	790	1	790
	CONNECTION AND TERMINATION	AWG#10	EA	64	2	128
	CONNECTION AND TERMINATION	AWG#12(GROUNDING)	EA	64	1	64
	JUNCTION BOX, NEMA-1	4" X 4" X 2" (1/2" & 3/4" KNOCK OUT) pigtail / wire connector / blank cover / label	EA	32	1	32
	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	750	1	750
	CONDUIT HANGER SUPPORT	3/4"	EA	125	1	125
☐CIRCUIT-L3 Booth Lighting Power	Single Conductor (THHN/THWN-2) - Stranded	AWG#10	FT	100	2	200
	Single Conductor (THHN/THWN-2) - Stranded	AWG#12(GROUNDING)	FT	100	1	100
	JUNCTION BOX, NEMA-1	4" X 4" X 2" (1/2" & 3/4" KNOCK OUT) pigtail / wire connector / blank cover / label	EA	2	1	2
	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	100	1	100
	CONDUIT HANGER SUPPORT	3/4"	EA	17	1	17
☐CIRCUIT-L4 Booth Lighting Power	Single Conductor (THHN/THWN-2) - Stranded	AWG#10	FT	130	2	260
	Single Conductor (THHN/THWN-2) - Stranded	AWG#12(GROUNDING)	FT	130	1	130
	JUNCTION BOX, NEMA-1	4" X 4" X 2" (1/2" & 3/4" KNOCK OUT) pigtail / wire connector / blank cover / label	EA	2	1	2
	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	130	1	130
	CONDUIT HANGER SUPPORT	3/4"	EA	22	1	22
☐CIRCUIT-L4 Booth Lighting Power	Single Conductor (THHN/THWN-2) - Stranded	AWG#10	FT	160	2	320
	Single Conductor (THHN/THWN-2) - Stranded	AWG#12(GROUNDING)	FT	160	1	160
	JUNCTION BOX, NEMA-1	4" X 4" X 2" (1/2" & 3/4" KNOCK OUT) pigtail / wire connector / blank cover / label	EA	1	1	1
	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	160	1	160
	CONDUIT HANGER SUPPORT	3/4"	EA	27	1	27
						0
☐ RECEPTACLE PLAN						0
☐CIRCUIT-R1	RECEPTACLE	120V, 20A DUPLEX.	EA	3	1	3
	JUNCTION BOX, NEMA-1	4" X 4" X 2" (1/2" & 3/4" KNOCK OUT) pigtail / wire connector / blank cover / label	EA	6	1	6
	Receptacle Metal Cover	1Gang 4" X 4"	EA	3	1	3
	Single Conductor (THHN/THWN-2) - Stranded	AWG#10	FT	170	2	340

No.	Description	Specification	Units	Calculation		Quantity
				dist.	piece	
	Single Conductor (THHN/THWN-2) - Stranded	AWG#12(GROUNDING)	FT	170	1	170
	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	160	1	160
	CONDUIT HANGER SUPPORT	3/4"	EA	27	1	27
☐CIRCUIT-R2	RECEPTACLE	120V, 20A DUPLEX.	EA	3	1	3
	JUNCTION BOX, NEMA-1	4" X 4" X 2" (1/2" & 3/4" KNOCK OUT) pigtail / wire connector / blank cover / label	EA	6	1	6
	Receptacle Metal Cover	1Gang 4" X 4"	EA	3	1	3
	Single Conductor (THHN/THWN-2) - Stranded	AWG#10	FT	190	1	190
	Single Conductor (THHN/THWN-2) - Stranded	AWG#12(GROUNDING)	FT	190	2	380
	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	180	1	180
	CONDUIT HANGER SUPPORT	3/4"	EA	30	1	30
☐CIRCUIT-R3	RECEPTACLE	120V, 20A DUPLEX.	EA	3	1	3
	JUNCTION BOX, NEMA-1	4" X 4" X 2" (1/2" & 3/4" KNOCK OUT) pigtail / wire connector / blank cover / label	EA	6	1	6
	Receptacle Metal Cover	1Gang 4" X 4"	EA	3	1	3
	Single Conductor (THHN/THWN-2) - Stranded	AWG#10	FT	290	2	580
	Single Conductor (THHN/THWN-2) - Stranded	AWG#12(GROUNDING)	FT	290	1	290
	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	190	1	190
	CONDUIT HANGER SUPPORT	3/4"	EA	30	1	30
☐CIRCUIT-R4	RECEPTACLE	120V, 20A DUPLEX.	EA	3	1	3
	JUNCTION BOX, NEMA-1	4" X 4" X 2" (1/2" & 3/4" KNOCK OUT) pigtail / wire connector / blank cover / label	EA	6	1	6
	Receptacle Metal Cover	1Gang 4" X 4"	EA	3	1	3
	Single Conductor (THHN/THWN-2) - Stranded	AWG#10	FT	280	2	560
	Single Conductor (THHN/THWN-2) - Stranded	AWG#12(GROUNDING)	FT	280	1	280
	ELECTRICAL METALLIC TUBING (EMT)+FITTING	3/4"	FT	190	1	190
	CONDUIT HANGER SUPPORT	3/4"	EA	30	1	30