

[B.O.Q]

PROJECT :POD INSPECTION
CONSTRUCTION PERIOD : '2026
SUBCONTRACTOR : TK ELECTRIC LLC

품 명 DESCRIPTION OF WORK		규 격 SPECIFICATION	단 위 UNIT	Bill of Quantity									비 고 REMARKS
				수 량 Q'ty	ITEM PRICE PER ITEM			단 가 Unit Price	금 액 Amount	ITEM PRICE PER CLASSIFICATION			
					MATERIAL	LABOR	EXPENSE			MATERIAL	LABOR	EXPENSE	
■POD INSPECTION													
1.POD INSPECTION													
□ POWER DIST RIBUTION PLAN													
NEW PANEL(PO-8001)	600 AMP 480/277V NEMA1	EA	1	12,145.00	680.00	769.50	13,594.50	13,594.50	12,145.00	680.00	769.50		
T TRANSFORMER (TRO-8001)	45KVA 480:208/120V)	EA	1	3,887.00	800.00	281.22	4,968.22	4,968.22	3,887.00	800.00	281.22		
NEW PANEL(PO-LDP)	125 AMP 208/120V 3PH,4W 42CKT	EA	1	1,600.00	340.00	116.40	2,056.40	2,056.40	1,600.00	340.00	116.40		
PVC CONDUIT , SCHEDULE 40	4"	FT	2000	8.11	11.00	1.15	20.26	40,519.30	16,225.76	22,000.00	2,293.54		
PVC CONDUIT , SCHEDULE 40 ELBOW	4"	FT	8	21.77	15.00	2.21	38.97	311.76	174.12	120.00	17.64		
MANHOLE (CONCRETE TYPE)	5'W x 5'H x 5'D	EA	5	7,200.00	5,800.00	780.00	13,780.00	68,900.00	36,000.00	29,000.00	3,900.00		
Asphalt cutting, Excavate, Concrete back filling, Asphalt finish	3'W x 4'H (Asphalt cutting) 110ft	FT	1000	16.40	9.80	1.57	27.77	27,772.00	16,400.00	9,800.00	1,572.00		
Single Conductor (THHN/THWN) – Stranded	AWG #350	EA	8800	9.84	5.72	0.93	16.49	145,143.68	86,592.00	50,336.00	8,215.68		
Single Conductor (THHN/THWN) – Stranded	AWG #1/0 (GROUNDING)	FT	2200	3.34	1.80	0.31	5.45	11,995.80	7,356.80	3,960.00	679.00		
LIQUIDTIGHT FLEXIBLE CONDUIT	1-1/2"	EA	6	6.18	8.54	0.88	15.60	93.58	37.06	51.23	5.29		
CONDUIT HANGER SUPPORT	1-1/2"	FT	4	12.38	14.66	1.62	28.66	114.64	49.52	58.64	6.48		
ELECTRICAL METALLIC TUBING (EMT)+ FITTING	1-1/2"	EA	10	3.10	4.27	0.44	7.81	78.13	31.02	42.69	4.42		
Single Conductor (THHN/THWN-2) – Stranded	AWG#4	FT	60	2.03	1.45	0.21	3.69	221.19	121.73	86.94	12.52		
Single Conductor (THHN/THWN-2) – Stranded	AWG#8(GROUNDING)	EA	20	0.59	0.91	0.09	1.58	31.67	11.77	18.11	1.79		
Single Conductor (THHN/THWN-2) – Stranded	AWG#1	FT	80	2.33	1.64	0.24	4.21	336.65	186.40	131.20	19.05		
Single Conductor (THHN/THWN-2) – Stranded	AWG#6(GROUNDING)	EA	20	0.87	1.04	0.11	2.02	40.49	17.40	20.80	2.29		
LIQUIDTIGHT FLEXIBLE CONDUIT	2"	FT	6	6.18	8.54	0.88	15.60	93.61	37.08	51.24	5.29		
ELECTRICAL METALLIC TUBING (EMT)+ FITTING	2"	EA	10	3.63	4.84	0.51	8.98	89.79	36.33	48.38	5.08		
CONDUIT HANGER SUPPORT	2"	FT	4	14.38	16.66	1.86	32.90	131.60	57.52	66.64	7.44		
PVC CONDUIT , SCHEDULE 40	1" (TR Ground)	EA	30	0.76	3.02	0.23	4.01	120.31	22.77	90.73	6.81		
Single Conductor (THHN/THWN-2) – Stranded	AWG#6(TR GROUNDING)	FT	30	0.87	1.04	0.11	2.02	60.73	26.10	31.20	3.43		
CONNECTION AND TERMINATION	#350 Kcmil COMPRESSION TYPE	EA	16	21.66	19.71	2.48	43.85	701.62	346.54	315.37	39.71		
CONNECTION AND TERMINATION	AWG#1/0 COMPRESSION TYPE	FT	4	9.23	11.68	1.25	22.17	88.65	36.91	46.73	5.01		
CONNECTION AND TERMINATION	AWG#1 COMPRESSION TYPE	EA	8	7.27	7.85	0.91	16.03	128.21	58.16	62.80	7.25		
CONNECTION AND TERMINATION	AWG#4 COMPRESSION TYPE	FT	6	5.38	5.82	0.67	11.87	71.21	32.27	34.91	4.03		
CONNECTION AND TERMINATION	AWG#6 COMPRESSION TYPE	EA	2	2.67	4.53	0.43	7.64	15.26	5.34	9.06	0.86		
CONNECTION AND TERMINATION	AWG#8 COMPRESSION TYPE	FT	4	1.58	4.09	0.34	6.02	24.06	6.33	16.37	1.36		
ALUMINUM CABLE TRAY (LADDER TYPE)	24"Width, 4"height, 9"rung spacing	EA	170	19.05	19.23	2.30	40.57	6,897.62	3,238.09	3,269.10	390.43		
ALUMINUM HORIZONTAL ELBOW (LADDER TYPE)	24"Width, 4"height, 9"rung spacing	FT	2	182.00	42.15	13.45	237.60	475.19	364.00	84.30	26.89		
ALUMINUM VERTICAL ELBOW (LADDER TYPE)	24"Width, 4"height, 9"rung spacing	EA	1	195.00	44.25	14.36	253.61	253.60	195.00	44.25	14.35		
CABLE TRAY SUPPORT	24" Width including beam clamp, square washer, unistrut, 2 rods(length:4ft~8ft, dia: 9/16"), etc	FT	29	78.09	51.90	7.80	137.79	3,995.89	2,264.61	1,505.10	226.18		
CABLE TRAY BONDING JUMPER	12"	EA	22	34.97	14.23	2.95	52.15	1,147.33	769.31	313.08	64.94		
[Sub Total]								330,472.69	188,331.94	123,434.87	18,705.88		
□ GROUNDING PLAN													
Single Conductor (THHN/THWN) – BARE	AWG#4/0(GROUNDING)	SET	540	5.27	4.47	0.58	10.33	5,576.45	2,844.97	2,415.84	315.64		
Excavation /w backfill	W8" x H24" MESH	FT	460	17.20	8.50	1.54	27.24	12,531.32	7,912.00	3,910.00	709.32		
PVC CONDUIT , SCHEDULE 40	1"	EA	40	1.48	2.05	0.21	3.73	149.36	59.03	81.88	8.45		
COPPER ROD	3/4 " X 10 '	EA	8	29.19	256.16	17.12	302.47	2,419.78	233.52	2,049.30	136.96		
EXOTHERMIC WELDING CONNECTION (COLUMN)	Mold , Ultra Shot , #90 , Weld to Column	FT	4	13.58	14.23	1.67	29.48	117.90	54.31	56.92	6.67		
EXOTHERMIC WELDING CONNECTION (GROUND ROD)	Mold , Ultra Shot , #90 , Weld to Rod	EA	8	13.58	14.23	1.67	29.48	235.82	108.63	113.85	13.34		
							-	-	-	-	-		
[Sub Total]								21,030.63	11,212.46	8,627.79	1,190.38		

[B.O.Q]

PROJECT :POD INSPECTION

CONSTRUCTION PERIOD : '2026

SUBCONTRACTOR : TK ELECTRIC LLC

품 명 DESCRIPTION OF WORK		규 격 SPECIFICATION	단 위 UNIT	Bill of Quantity								비 고 REMARKS	
				수 량 Q'ty	ITEM PRICE PER ITEM			단 가 Unit Price	금 액 Amount	ITEM PRICE PER CLASSIFICATION			
					MATERIAL	LABOR	EXPENSE			MATERIAL	LABOR		EXPENSE
☐ MECHANICAL POWER PLAN													
CONDUIT HANGER SUPPORT	2-1/2"	SET	15	14.38	15.66	1.80	31.84	477.63	215.70	234.90	27.03		
CONDUIT HANGER SUPPORT	3/4"	SET	111	12.38	14.66	1.62	28.66	3,181.52	1,374.18	1,627.26	180.08		
CONNECTION AND TERMINATION	AWG#3/0 COMPRESSION TYPE	EA	18	11.68	9.49	1.27	22.44	403.94	210.31	170.77	22.86		
CONNECTION AND TERMINATION	AWG#6 COMPRESSION TYPE	FT	6	2.67	4.53	0.43	7.63	45.79	16.02	27.18	2.59		
CONNECTION AND TERMINATION	AWG#10 COMPRESSION TYPE	EA	132	0.76	3.02	0.23	4.01	528.89	100.32	398.64	29.93		
DISCONNECT SWITCH	480V , 30 NEMA 1 (Without Fuse)	FT	6	142.85	77.63	13.23	233.71	1,402.24	857.12	465.75	79.37		
ELECTRICAL METALLIC TUBING (EMT) ELBOW	2-1/2"	EA	3	22.50	86.85	6.56	115.91	347.73	67.50	260.55	19.68		
ELECTRICAL METALLIC TUBING (EMT)+ FITTING	2-1/2"	FT	90	5.52	9.11	0.88	15.51	1,395.67	496.95	819.72	79.00		
ELECTRICAL METALLIC TUBING (EMT)+ FITTING	3/4"	FT	540	1.16	2.99	0.25	4.40	2,375.46	626.40	1,614.60	134.46		
LIQUIDTIGHT FLEXIBLE CONDUIT	3/4"	FT	72	1.58	2.82	0.26	4.66	335.80	113.76	203.04	19.00		
LIQUIDTIGHT FLEXIBLE CONDUIT CONNECTOR	3/4"	EA	24	4.25	3.14	0.44	7.83	188.00	102.00	75.36	10.64		
Multi Conductor (THHN/THWN-2) – Stranded	(3PH+ 1N+ GROUNDING) AWG#10	FT	2130	1.48	1.14	0.16	2.78	5,910.93	3,152.40	2,423.95	334.58		
Single Conductor (THHN/THWN-2) – Stranded	AWG#3/0	FT	1620	4.47	0.97	0.33	5.77	9,351.10	7,247.53	1,574.27	529.30		
Single Conductor (THHN/THWN-2) – Stranded	AWG#6(GROUNDING)	FT	540	0.87	1.04	0.11	2.02	1,093.28	469.80	561.60	61.88		
[Sub Total]								27,037.98	15,049.99	10,457.59	1,530.40		
☐ LIGHTING PLAN													
LED FLOOD LIGHTING	LED 95W	EA	36	308.00	225.96	32.04	566.00	20,376.04	11,088.00	8,134.68	1,153.36		
LED LIGHTING Canopy	LED 20W	EA	14	90.00	129.12	13.15	232.27	3,251.76	1,260.00	1,807.70	184.06		
WALL MOUNTED	LED 80W	EA	4	330.00	250.00	34.80	614.80	2,459.20	1,320.00	1,000.00	139.20		
EMERGENCY EXIT LED SIGN	LED 2W	EA	12	103.53	64.50	10.08	178.11	2,137.34	1,242.36	774.00	120.98		
CONDUIT HANGER SUPPORT	3/4"	SET	375	12.38	14.66	1.62	28.66	10,748.40	4,642.50	5,497.50	608.40		
CONNECTION AND TERMINATION	AWG#10	EA	288	3.02	2.02	0.30	5.35	1,540.88	871.05	582.61	87.22		
CONNECTION AND TERMINATION	AWG#12(GROUNDING)	EA	144	2.98	2.00	0.30	5.28	760.14	429.12	288.00	43.02		
ELECTRICAL METALLIC TUBING (EMT)+ FITTING	3/4"	FT	2240	1.16	2.99	0.25	4.40	9,853.76	2,598.40	6,697.60	557.76		
JUNCTION BOX, NEMA-1	4" X 4" X 2" (1/2" & 3/4" KNOCK OUT) pigtail / wire connector / blank cover / label	EA	83	8.90	35.80	2.68	47.38	3,932.70	738.70	2,971.40	222.60		
Single Conductor (THHN/THWN-2) – Stranded	AWG#10	FT	4600	0.39	0.97	0.08	1.44	6,631.36	1,794.00	4,462.00	375.36		
Single Conductor (THHN/THWN-2) – Stranded	AWG#12(GROUNDING)	FT	2300	0.29	0.95	0.07	1.31	3,023.12	667.00	2,185.00	171.12		
WALL SWITCH	120-277V , SINGLE POLE	EA	2	10.56	56.93	4.05	71.53	143.06	21.12	113.85	8.09		
[Sub Total]								64,857.76	26,672.25	34,514.34	3,671.17		
☐ RECEPTACLE PLAN													
CONDUIT HANGER SUPPORT	3/4"	SET	117	12.38	14.66	1.62	28.66	3,353.50	1,448.46	1,715.22	189.82		
ELECTRICAL METALLIC TUBING (EMT)+ FITTING	3/4"	FT	720	1.16	2.99	0.25	4.40	3,167.28	835.20	2,152.80	179.28		
JUNCTION BOX, NEMA-1	4" X 4" X 2" (1/2" & 3/4" KNOCK OUT) pigtail / wire connector / blank cover / label	EA	24	8.90	35.80	2.68	47.38	1,137.16	213.60	859.20	64.36		
RECEPTACLE	120V , 20A DUPLEX.	EA	12	15.38	62.67	4.68	82.73	992.79	184.56	752.04	56.19		
Receptacle Metal Cover	1Gang 4" X 4"	EA	12	2.54	2.11	0.28	4.93	59.14	30.48	25.32	3.34		
Single Conductor (THHN/THWN-2) – Stranded	AWG#10	FT	1860	0.39	0.97	0.08	1.44	2,681.37	725.40	1,804.20	151.77		
Single Conductor (THHN/THWN-2) – Stranded	AWG#12(GROUNDING)	FT	930	0.29	0.95	0.07	1.31	1,222.39	269.70	883.50	69.19		
[Sub Total]								12,613.63	3,707.40	8,192.28	713.95		
☐ RENTAL EQUIPMENT													
SCISSRO LIFT	24'~26'	EA	3	-	-	1,200.00	1,200.00	3,600.00	-	-	3,600.00		
BOOM LIFT	27'	EA	1	-	-	1,900.00	1,900.00	1,900.00	-	-	1,900.00		
EXCAVATOR	18000lb	EA	1	-	-	3,800.00	3,800.00	3,800.00	-	-	3,800.00		
							-	-	-	-	-		
[Sub Total]								9,300.00	-	-	9,300.00		
[Total]													